

CONTRACT AMENDMENT

NO. 2

Project: City of Vicksburg Drainage & Sewer Imp. Date: July 23, 2018
Owner: City of Vicksburg
Contractor: Riverside Construction Co., Inc.

The contract, dated December 6, 2017, between the above listed parties, is hereby amended as set forth below. Description of and reason for amendment:

- Additional 5 working days added to contract time due to City's agreement to extend time on the Manship Circle site to accommodate property owner's requests that were outside original scope of work.
- To amend final quantities to reflect the actual over-runs and under-runs experienced on the project.

Contract Amount is Amended as Follows:

Contract Time is Amended as Follows:

Present Contract Amount	<u>\$267,544.00</u>	Present Completion Date	<u>75 Working Days</u>
Net Change in Contract	<u>-\$25,372.80</u>	Net Change-No. of Days	<u>5</u>
Amended Contract Amount	<u>\$242,171.20</u>	Amended Completion Date	<u>80 Working Days</u>

Recommended by _____


Engineer

Approved by _____


Contractor

PUTME GANDE.

Approved by _____

Owner

**CONTRACT AMENDMENT NO. 2
CITY OF VICKSBURG - DRAINAGE AND STORM SEWER IMPROVEMENTS
VICKSBURG, MS**

PAY ITEM NO.	DESCRIPTION	PRESENT CONTRACT QUANTITY	UNIT	NET CHANGE IN QUANTITY	AMENDED CONTRACT QUANTITY	AMENDED CONTRACT AMOUNT		INCREASE OR DECREASE
						UNIT PRICE	AMOUNT	
BASE BID								
S-200-A	Mobilization	1.00	LS	0.00	1.00	\$9,400.00	\$9,400.00	\$0.00
S-201-A	Cleaning and Grubbing	4.00	ACRE	0.00	4.00	\$500.00	\$2,000.00	\$0.00
S-202-B	Removal of Pipe all Sizes	96.00	LF	(30.00)	66.00	\$10.00	\$660.00	(\$300.00)
901-202-Z	Removal of Sediment and Debris from Culverts and Cross Drain	7.00	EA	0.00	7.00	\$10,500.00	\$73,500.00	\$0.00
S-203-A	Unclassified Excavation (PM)	786.00	CY	0.00	786.00	\$5.75	\$4,519.50	\$0.00
S-203-E	Borrow Excavation (Contractor Furnished LVM, Class C)	480.00	CY	0.00	480.00	\$15.50	\$7,440.00	\$0.00
S-203-H	Excess Excavation (LVM)	7,662.00	CY	(556.00)	7,126.00	\$9.00	\$64,134.00	(\$5,004.00)
S-206-A	Structure Excavation	24.00	CY	(24.00)	0.00	\$15.50	\$0.00	(\$372.00)
S-226-A	Solid Sodding	450.00	SY	0.00	450.00	\$5.00	\$2,250.00	\$0.00
S-227-A	Excelsior Blanket	150.00	SY	(150.00)	0.00	\$3.75	\$0.00	(\$562.50)
901-S-228-A	Hydroseeding	4.00	ACRE	0.00	4.00	\$2,000.00	\$8,000.00	\$0.00
S-233-A	Silt Fence	10,700.00	LF	(7017.00)	3683.00	\$2.60	\$9,575.80	(\$18,244.20)
907-237-A	Wattles, 12"	50.00	EA	(50.00)	0.00	\$5.75	\$0.00	(\$287.50)
S-601-A	Class "B" Structural Concrete	4.81	CY	6.69	11.50	\$2,000.00	\$23,000.00	\$13,980.00
S-602-A	Reinforcing Steel	184.80	LB	(184.80)	0.00	\$2.50	\$0.00	(\$462.00)
S-603-PE	Installation of 24" Corrugated Polyethylene Pipe	40.00	LF	20.00	60.00	\$55.00	\$3,300.00	\$1,100.00
S-603-C	24" Reinforced Concrete Pipe, Class III	20.00	LF	(20.00)	0.00	\$67.00	\$0.00	(\$1,340.00)
S-603-C-B	24" Reinforced Concrete Pipe, Eind Section	1.00	EA	0.00	1.00	\$940.00	\$940.00	\$0.00
*S-603-PE	36" Corrugated Polyethylene Pipe	60.00	LF	0.00	60.00	\$80.00	\$4,800.00	\$0.00
S-815-A	Loose RipRap, (Size 300 lb)	615.00	TON	(195.74)	419.26	\$55.00	\$27,251.90	(\$12,723.10)
S-815-E	Geotextile under RipRap, Type V, AOS 0.21-0.43	763.00	SY	(223.00)	560.00	\$2.50	\$1,400.00	(\$567.50)
TOTAL							\$242,171.20	(\$25,372.80)